

**ICAR- CENTRAL INSTITUTE OF FISHERIES EDUCATION**

(Deemed University)

PanchMarg, Off.Yari Road, Versova,Andheri(west).

Mumbai – 400 061.

F. No. 32(164)/Works/2020-21/F-25

Date : 02.03.2021

**OPEN TENDER NOTICE**

**Name of the work : Replacement of damaged doors and other miscellaneous carpentary works in Boys Hostel at new campus of ICAR- CIFE Mumbai. reg-**

The Sr.Adminstrative Officer, Central Institute of Fisheries Education (CIFE) Mumbai - 400 061 invites Limited tender on CPP portal for the work titled **“Replacement of damaged doors and other miscellaneous carpentary works in Boys Hostel at new campus of ICAR- CIFE Mumbai.”** from eligible and approved Govt. Registered Contractors i.e. CPWD/PWD/BSNL/MTNL/Any Other Govt. Organizations.

**IMPORTANT INFORMATION & DATES FOR BIDDERS**

<b>Date for Issue/Publishing the tender</b>	<b>: From 02/03/ 2021 at 15.00 hrs</b>
<b>Last date for receiving the Tender</b>	<b>: 09/03/2021 Up to 1500 hrs. (07 Days from date of issue/publish</b>
<b>Date of opening of Tender</b>	<b>: 10/03/2021 At 1500 hrs. (Next day of the last date of bid submission</b>
<b>Date of completion of Work</b>	<b>: 15 days from award of work order.</b>
<b>Earnest Money Deposit (EMD)</b>	<b>: Rs.14,000/- (Rupees Fourteen thousand only) in the form of Demand Draft draw in favour of “ICAR Unit CIFE Mumbai”.</b>
<b>Original DD EMD should be submitted to OIC (Works), CIFE Mumbai, on behalf of Director, ICAR-CIFE, Mumbai before the bid/tender submission end of date and time.</b>	

The Sr.Adminstrative Officer of the institute reserves the right to accept or reject any or all tender without assigning any reasons whatsoever. No correspondence shall be entertained in this regards.

**Senior Administrative Officer**

**INSTRUCTIONS TO BIDDERS, TERMS & CONDITIONS OF CONTRACT**  
**FOR EXECUTION OF WORKS**

**(1) The following list of documents are to be scanned and uploaded within the period of bid submission with the tender/bid, failing which the tender shall be rejected out rightly:**

- 1.1 Demand Draft of EMD. However, original D.D. of EMD should be submitted to OIC (W), CIFE Mumbai, on behalf of Director, ICAR-CIFE Mumbai before the bid submission end date and time.
  - 1.2 A copy of contractor's valid registration with CPWD/ PWD/ MES/ BSNL/ MTNL/ P & T/ All India Radio/ PSU/ Any Other Govt. Organizations.
  - 1.3 Certificate of Registration for GST, Sales Tax / VAT and acknowledgement of up to date filed return if required.
  - 1.4 Experience of two works of similar nature of during last three years with satisfactory completion.
  - 1.5 A Scan copy of PAN Card
  - 1.6 A Photostats (i. e Xerox) copy of blank cheque for making payment by RTGS method.
2. The work shall be executed as per CPWD specifications.
  3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
  4. Tender Documents accompanied by an Earnest Money Deposit (EMD) amounting to **Rs.14,000/- (Rupees Fourteen thousand only)** should be paid in the form of crossed Demand Draft drawn in favour of "**ICAR Unit, CIFE, Mumbai**".
  5. Any other item to be required at site to complete the work will be executed as per the rates quoted on DSR-2018.
  6. The rates shall remain valid for 90 days from the date of opening of Tender.
  7. Tender received after due date and time shall not be entertained.
  8. Contractor/ agency should be experienced in above said work.
  9. The EMD of unsuccessful bidders will be returned within 15 days from the date of award of work order to successful bidder.
  10. **The successful bidder has to pay Security Deposit amounting to 10% of the quoted amount within 5days after accepting the work order of the said work.** The security deposit will be released only after six months from the date of successful completion of work.
  11. The defect liability period is 6 months. Any defect arising in the defect liability period is to be rectified by the contractor without any extra cost, failing which the same shall be done departmentally at the "**risk and cost**" of the contractor and the amount of expenditure shall be deducted from the security deposit.
  12. The quoted rates should be inclusive of cost of material, carriages, whatsoever, storage, watch and ward, wastages, etc. The quoted rates shall not be increased under any circumstances.
  13. TDS will be deducted at source from the bill as per rules.

14. The Institute will not supply any tools, equipments, materials storage. The contractor has to make their own arrangement.
15. The work shall start within 2 days from the date of award and complete within the stipulated time failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum up to 10%. The work must be completed within the specified time period.
16. The EMD submitted by the bidder is liable to be forfeited by the Institute, if the selected firm/bidder fail to commence the work within two days from the date of receipt of work order.
17. Works are to be executed strictly as per the specifications mentioned in the Tender Document failing which work shall be rejected.
18. The material used for renovation must be approved by the Officer In-charge (Works)/ Engineer in-charge before using, failing which works shall be rejected.
19. The agency has to abide by all rules and regulations pertaining to labour act. The contractor has to take all necessary steps for the welfare measures of labours employed by him at the site.
20. The agency will be fully responsible for providing medical facilities to their labourers in case of any accident, etc. Matters related to labour welfare/problems should be dealt by the contractor only. CIFE, Mumbai shall not be responsible in such matters.
21. Taxes, GST etc. if any, should be clearly mentioned in the quotation, failing which it will be presumed that the quoted rates are inclusive of all taxes. No additional tax will be allowed if the same is not mentioned in the quotation/tender/bid.
22. The tenders/bidders in their own interest are instructed to visit the site for understanding the site conditions, nature of work, etc.
23. Quantity of Work awarded may be increased or decreased with the approval of Competent Authority.
24. The Sr.Adminstrative Officer, ICAR-CIFE, Mumbai reserves the right to accept or reject any or all tender / all tenders without specifying any reason whatsoever. No correspondence shall be entertained in this regard. The decision of the Sr.Adminstrative Officer, ICAR-CIFE, Mumbai shall be final and binding on all concerned in such matters.

**Yours faithfully,**

**Senior Administrative Officer**

**ICAR-CENTRAL INSTITUTE OF FISHERIES EDUCATION****(DEEMED UNIVERSITY, ICAR),****MUMBAI – 400 061****BILL OF QUANTITY****Name of work**—Replacement of damaged doors and other miscellaneous carpentary work in Boys Hostel at new campus of CIFE Mumbai.

<b>S.N</b>	<b>Details of works</b>	<b>DSR Item No.</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
1	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) : (a) With F.P.S. (non modular) bricks	6.3.1 / Pg-108	1.00	cum	7722.65	7722.65
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (a) Sal wood	9.1.2 / Pg-146	0.10	cum	105327.2	10532.72
3	Providing and fixing ISI marked flush door shutters conforming to IS :2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters (a) 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws <b>(Century make or equivalent)</b>	9.21.1 / Pg-150	30.00	sqm	1886.7	56601.00
4	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels (a) Granite of any colour and shade (1) Area of slab upto 0.50 sqm	8.2.2.1 / Pg-123	3.00	sqm	4217.35	12652.05
5	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge (a) Granite work	8.3.2 / Pg-123	3.00	Metre	376.25	1128.75

6	providing and fixing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	9.23 / pg-148	30.00	sqm	401.40	12042.00
7	Providing and fixing IS : 12817 marked stainless steel butt hinges (heavy weight) with stainless steel screws etc. complete : (a)125x64x2.50 mm <b>(ISI make)</b>	9.71.1 / Pg-153	20.00	Each	95.90	1918.00
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete : <b>(Archies make or equivalent)</b>					
8(a)	(a)250x10 mm	9.97.2 / Pg-159	20.00	Each	103.55	2071.00
9	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete (a)125mm <b>(Archies make or equivalent)</b>	9.100.1 / Pg-160	40.00	each	59.65	2386.00
10	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete (a)300 x 16mm <b>(Archies make or equivalent)</b>	9.96.1 / pg-159	20.00	Each	257.15	5143.00
11	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt / suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS :2046 Type S, including cost of adhesive of approved quality(a)1.0 mm thick <b>(Century make or equivalent)</b>	9.127.2 / pg-165	60.00	sqm	717.65	43059.00
12	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	14.75 / Pg-251	5.00	sqm	512.00	2560.00
13	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. (a)single rubber stopper <b>(Archies make or equivalent)</b>	9.101.1 / Pg-160	20.00	Each	33.95	679.00

14	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead (a)Of area 3 sq. metres and below	15.12.1 / Pg-259	20.00	each	274.5	5490.00
15	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	15.60 / Pg-263	5.00	CUM	138.85	694.25
16	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size,including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. <b>(Jindal make or equivalent)</b>					
16a	(a)For fixed portion.(1)Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC15)	21.1.1.1 / Pg-381	3.00	kg	423.95	1271.85
16b	(a)For fixed portion.(1)Powder coated aluminium (minimum thickness of powder coating 50 micron)	21.1.1.2 / Pg-381	25.00	kg	456.3	11407.50
16c	(b)For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required. (1)Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC15)	21.1.2.1 / Pg-381	3.00	kg	513.4	1540.20
16d	(b)For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required. (1)Powder coated aluminium (minimum thickness of powder coating 50 micron)	21.1.2.2 / Pg-381	25.00	kg	546.35	13658.75

17	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P.brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment). <b>(Jindal make or equivalent)</b>	21.17 / Pg-384	5.00	kg	519.85	2599.25
18	Providing and fixing to existing door frames:(a)30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames.	9.122.1 / Pg-164	10.00	kg	3465.05	34650.50
<b>Non-Schedule items</b>						
E-1	Removing of existing door frames from wall and refixing it with proper hold fasts and anchor fastners (6") proper aligning it with the wall, also providing and applying bituminous paint on wall side of the door frame or as instructed by engineer-incharge	N.S	10.00	Each	1500.00	15000.00
E-2	Providing and fixing zinc alloyed (white/brown powder coated) touch lock for aluminum sliding window with necessary screws etc. complete	N.S	10.00	Each	300.00	3000.00
E-3	Providing and fixing PVC roller for aluminium sliding window with necessary screws etc. complete	N.S	20.00	Each	100.00	2000.00
E-4	Providing and fixing stoarge cabinet made of 19mm thick marine plywood including shelf of 400mm to 450mm centre to centre and shutters both made of 19mm thick marine plywood, back covered with 6mm marine plywood and storage unit is finished externally with approved quality 1mm thick laminate including finishing inner sides and back side by two coat of french polish with necessary fixtures and fastenings as per detailed design and drawing etc complete.(a)Marine Plywood <b>(Garnier/Century make or equivalent)</b> Laminate- <b>(Century make or equivalent)</b>	N.S	17.00	Sqm	14000.00	238000.00

E-5	Removing and refixing of aluminum partition in the washing area of the kitchne mess including fixing the loose section and ackalite sheet in boys hostel at new campus.	N.S	Job	L.S	2000.00	2000.00
E-6	Providing and fixing backalite sheet of 4mm thickness to the partition of washing area and wherever required.	N.S	4.00	Sqm	750.00	3000.00
					Total of schedule items in Rs.	229807.47
					Add cost index 22.88%	52579.95
					Total of non-schedule items in Rs.	263000.00
					Grand Total in Rs.	<b>545387.42</b>
					<b>say Rs.</b>	<b>545387.00</b>

(Amount in words: Rupees Five Lakhs Forty-five thousand three hundred and Eighty-seven only)

Percentage above or Below or at par quoted by bidder in numbers \_\_\_\_\_ %

Percentage above or Below or at par quoted by bidder in words \_\_\_\_\_

Date:

Sign Of Bidder with Seal